

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30717
Name: Downing Nelson Oil Co., Inc
Address 1: P.O. Box 372
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: RON NELSON
Phone: (785) 621-2610
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 195-22,614-00-00
Spot Description: 40' E of
N2 SW SW Sec. 10 Twp. 13 S. R. 21 East West
990 Feet from North / South Line of Section
700 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: TREGO
Lease Name: DEUTSCHER Well #: 3-10
Date Well Completed: 07/01/09
The plugging proposal was approved on: 06/30/09 (Date)
by: Bruce Bayse (KCC District Agent's Name)
Plugging Commenced: 6:15 PM 07/01/09
Plugging Completed: 8:45 PM 07/01/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8"	216.08	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in filling the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1590' with 25 sks, 2nd Plug @ 780' with 100 sks, 3rd Plug @ 275' with 40 sks, 4th Plug @ 40' with 10 sks, 30 sks in rat hole, 15 sks in mouse hole, total 220 sks 60/40Poz 4% Gel with 1/4# CF/sk cemented by Allied, completed at 8:45 PM 07/01/09.

Circulated 1st plug 15 minutes with 56Vis Mud, plugs displaced with mud

Plugging Contractor License #: 31548 Name: DISCOVERY DRILLING CO., INC.
Address 1: PO Box 763 Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 623-2920
Name of Party Responsible for Plugging Fees: Downing Nelson Oil Co., Inc
State of Kansas County, Ellis, ss.
Alan Downing Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Alan Downing