

15-163-20360-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*MP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-20-72  
MAR 20 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Hummon Oil Company

Complete Address 821 Union National Bldg., Wichita, Kansas 67202

Lease Name Rempe Well No. 1

Location SE SE NW Sec. 17 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3784'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

*RT KCC*

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 11:30 A Day 16 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3784 8 5/8 csg set at 209' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

4 1/2 csg set at 3779' cw 150 sk cmt.

4 1/2 csg PBTD 3600' with perf. (3578)

Set 4 1/2 wood plug at 3500' -poured 25' sd -dumped 4 sk cmt W/dump bailer. (3450-3500)

Cutoff and recovered 1750' of 4 1/2 csg.

Pumped down 8 5/8 csg with 17 sk gel & water W/500 lbs hulls, 70 sk cmt, 8 sk

gel & water, released 8 5/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo Messing*  
Well Plugging Supervisor

DATE 3-23-72

INV. NO. 5391-W