

<sup>40</sup>  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
10-29-64  
OCT 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Davis Bros

Complete Address: 510 Mc Farlin Bldg Tulsa, Okla

Lease Name Ordway Well No. E-1

Location SE SW NE Sec. 20 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3741

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Operation Completed: Hour 3PM Day 22 Month 10 Year 64

The Above well was plugged as follows:

~~8 5/8" 192' circulated with cement - 5 1/2" 3738' with 200 sax cement behind  
PB to 3608' - Perf 3548'~~

~~Filled with sand to 3530', set 4 sax cement with dump bailer - pulled  
2531' 5 1/2" to 550' - circulated hole with heavy gel mud through 5 1/2" at 550'  
(20 sax gel) pulled pipe to 480', displaced 20 sax cement through 5 1/2" at  
480', heavy mud to 200' - displaced 20 sax cement through 5 1/2" at 200', heavy  
mud to 35' cement 35' to bottom cellar.~~

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 10/29/64

INV. NO. 73-11

Signed: Edna P. [Signature]  
Well Plugging Supervisor