

15-163-20701-0000

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CONSERVATION DIVISION
9-6-77
SEP 06 1977
CONSERVATION DIVISION
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,701 (of this well)

Operator's Full Name F & M Oil Co., Inc

Complete Address 505 Union Center, Wichita, Ks.

Lease Name Andreson Well No. 1

Location SE NW NW Sec. 20 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3712'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 11:45 P Day 4 Month 9 Year 1977

The above well was plugged as follows:

RTD 3712' 8 5/8 csg set 264' cwc 180 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 9-7-77

INV. NO. 5784-0