

15-163-20366-0000

Form CP-3
Rev. 6-4-68

KANSAS

of STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
4-26-71
APR 26 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beacon Resources Corporation

Complete Address 1000 Century Plaza Wichita, Kansas

Lease Name Ordway Well No. 1

Location SE SW SE Sec. 21 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3688'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 9:30 A Day 24 Month 4 Year 1971

The above well was plugged as follows:

RTD 3688' 8 5/8 csg set at 208' cwc Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

4/29/71

INV. NO.

3615-W

Signed:

Well Plugging Supervisor

Ben F. Massey