

15-163-20089-0000

Form CP-3  
Rev. 6-9-67

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

1-2-68  
JAN 2 1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

JAN 5 1968

Operator's Full Name C. R. Porter Trucking Service

Complete Address P. O. Box 185 Plainville, Ks.

Lease Name Garvert "B" Well No. 2

Location C W/2 W/2 NE Sec. 22 Twp. 10 Rge. 18 (E) (W) X

County Rooks Total Depth 3700'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Woodman-Iannitti Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 8:30 A Day 31 Month 12 Year 1967

**The above well was plugged as follows:**

RTD 3700' 8 5/8 csg set at 188' cwc 125 sc. Cementing Material 50-50 Poz W/6 % gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: Rio J. Mason  
Well Plugging Supervisor

DATE 1-3-68

INV. NO. 7028-W