

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 7 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Parks of Gabbert - Jones Drlg. has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Price Exploration Co.

Complete Address: 404 Oil Capitol Bldg., Tulsa, Okla.

Lease Name: Rempe "A" Well No. 1

Location: C NW SE SW Sec. 17 Twp. 10 Rge. (E)(W) 18

County: Rooks Total Depth 3790' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Parks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with  
2 sk cmt.

Very truly yours,

Ben J. Massey  
 Conservation Division Agent