

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

1-2-68
JAN 2 1968

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

JAN 5 1968

Dear Sir:

Mr. Flake of Woodman-Iannitti Drlg. has this

date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: C. R. Porter Trucking Service

Complete Address: P. O. Box 185 Plainville, Ks.

Lease Name: Garvert "B" Well No. 2

Location: C W/2 W/2 NE Sec. 22 Twp. 10 Rge. 18 (E)(W) X

County: Rooks Total Depth 3700 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with

2 sc cement.

Very truly yours;

Leo F. Massey
Conservation Division Agent