


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 3 Twp. 10S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C SE NE
Lease Owner Davis Bros. - Transit Corporation
Lease Name Korton "A" Well No. 1
Office Address 1516 Liberty Bank Bldg., Oklahoma City, Okla. 73102
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 28 1964
Application for plugging filed January 28 1964
Application for plugging approved January 28 1964
Plugging commenced January 28 1964
Plugging completed January 28 1964
Reason for abandonment of well or producing formation No Production

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	171'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550', set plug, cemented with 20 sacks

Filled hole with heavy mud to 165', set plug, cemented with 20 sacks

filled hole with heavy mud to 35', set plug, cemented with 10 sacks to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
2-27-64
FEB 27 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma 73102

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 19 64

My commission expires January 3, 1966

Paul G. [Signature]
Notary Public.



15-163-01066-0000

DRILLER'S WELL LOG

Davis Bros. - Transit Corporation

Korton "A" # 1 located in
C SE NE, Section 3-108-19W
Rooks County, Kansas

Commenced: January 17, 1964
Completed: January 28, 1964
Elevation:

Casing: 8 5/8" @ 171'

<u>Formation</u>	<u>From</u>	<u>To</u>
Sand	0	35
Shale	35	160
Shale and sand	160	1335
Shale and Red Bed	1335	1503
Anhydrite	1503	1545
Shale and shells	1545	1900
Shale, shells and salt	1900	2100
Shale and lime	2100	2300
Lime and shale	2300	2505
Shale w/lime streaks	2505	2680
Shale and lime	2680	3230
Lime	3230	3275
Lime and shale	3275	3412
Lime	3412	3430
Lime and shale	3430	3445
Lime	3445	3515
Lime and shale	3515	3570
Lime	3570	3590
Lime shale and chert	3590	3650
Lime	3650	3677
Lime, chert and shale	3677	3681
Arbuckle	3681	3706 T.D.

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1964
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing to be a true and correct
driller's log of the formations encountered in the above well.

Subscribed and sworn to before me
this 25th day of February, 1964

TRANSIT CORPORATION

By L. J. Trues

My commission expires Jan. 3, 1966

Paul E. Gathers
Notary Public