

15-163-00531-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 3 Twp. 10S Rge. 19 ~~XX~~ (W)

Location as "NE/CNW/SE" or footage from lines C-SW-SW-NE
Lease Owner Sunray Oil Corporation
Lease Name Sparks Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 12 1953
Application for plugging filed October 12 1953
Application for plugging approved October 13 1953
Plugging commenced October 12 1953
Plugging completed October 12 1953
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3719 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka		3104		8 5/8	285	none
Heebner		3315				
Toronto		3334				
Lansing-Kansas City		3354				
Base Kansas City		3582				
Cherty Conglomerate		3606				
Simpson Dolomite		3624				
Arbuckle		3669				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

TD 3719', mudded hole to 240' and placed 20 sax cement. Mudded hole to 40' and placed 10 sax cement. Dry hole plugged and abandoned.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H & H Drilling Company
Address Wichita, Kansas

STATE OF Kansas COUNTY OF Barton ss.
Robert K. Crouch (employee of owner) or (~~by not a party to~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1953

My commission expires December 24, 1956

Notary Public.

24-2675-8 2-52-20M

PLUGGING
FILE SEC 3 10 19W
BOOK PAGE 135 LINE 25

10-21-53
CONSERVATION DIVISION
Wichita, Kansas

CERTIFIED DRILLER'S LOG

COMPANY: SUNRAY OIL CORPORATION LEASE: SPARKS #1
 CONTRACTOR: H & H DRILLING COMPANY LOCATION: SW SW NE
 COMMENCED: 9-28-53 3-10S-19W
 Rooks County, Kansas
 COMPLETED: 10-12-53 CASING:
 285' of 8-5/8" cemented with 225 sacks
 ELEVATION: 2162 RB
 POTENTIAL: D&A

<u>FORMATION</u>	<u>DEPTH</u>
Sand	0 - 100
Sand & Shale	100 - 180
Blue Shale	180 - 275
Shale & Shells	275 - 287
Shale	287 - 750
Shale, Salt & Sand	750 - 1300
Red Bed Shale	1300 - 1615
Shale & Lime	1615 - 2265
Lime	2265 - 2653
Lime & Shale	2653 - 2825
Lime	2825 - 2835
Lime & Shale	2835 - 3318
Lime	3318 - 3719
RTD	3719

I hereby certify that this is a true and correct copy of the above log to the best of my knowledte.

R. E. Hartman
 R. E. HARTMAN

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 14th day of Oct., 1953

Ella Press
 Notary Public

My Commission Expires: August 25, 1956

PLUGGING
 FILE SEC 3 T 10 R 19W
 BOOK PAGE 135 LINE 25

REGISTRATION DIVISION
 Kansas