


15-163-00527-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 4 Twp. 10S Rge. 19 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE/4 SW/4 SE/4
Lease Owner Walters Drilling Co., Inc.
Lease Name Joy Well No. 1
Office Address 510 Orpheum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 28, 19 53
Application for plugging filed (verbal) March 28, 19 53
Application for plugging approved (verbal) March 28, 19 53
Plugging commenced March 28, 19 53
Plugging completed March 28, 19 53
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3760' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	None	0	147'	8 5/8	147'	None
Cemented with 100 sacks cement and 1 Cal. Chloride. No oil string run - dry and abandoned.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 145' with 15 sacks cement and 1 sack Hulls

Set top plug at 40' with 10 sacks cement and 1/2 sack Hulls

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co., Inc.
Address 510 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters
510 Orpheum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of March, 19 53

Carlisle Ruedrich
Notary Public.

My commission expires March 10, 1956

24-2675-S 2-52-20M
PLUGGING
FILE SEC 4 T 10 R 19W
BOOK PAGE 88 LINE 8

RECEIVED
STATE CORPORATION COMMISSION
4-1-53
APR 1 1953
CONSERVATION DIVISION
Wichita, Kansas

JOY NO. 1

Location: SE SW SE Sec. 4-10S-19W Rooks County, Kansas Date Spudded: 3-16-53
 Operator: Walters Drilling Co., Inc. Rotary Completion: 3-28-53
 Contractor: Walters Drilling Co., Inc. Elevation: 2168 Gr
 Surface Casing: 8 5/8" set at 147' with 100 sacks cement and 1 Gal. Chloride 2170 DF
 Oil String: None. D & A 2172 KB

L O G

(Figures indicate bottom of formation)

Surface	0 to 147
Shale and Shells	890
Sand, Shale and Shells	1365
Shale and Shells	1555
Anhydrite	1596
Shale and Shells	2380
Shale and Lime	3464
Lime (Cherty)	3490
Lime	3650
Conglomerate	3690
Cherty Lime and Shale	3713
Lime and Shale	3760
Total Depth (Rotary)	3760

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO., INC.
By Robert F. Walters

Subscribed and sworn to before me this 30th day of March, 1953.

Pauline Rudwick
Notary Public

My commission expires March 10, 1956

PLUGGING
 FILE SEC. 4 T. 10 R. 19W
 BOOK PAGE 28 LINE 8

RECORDED
 INDEXED
 MARCH 31 1953
 COUNTY CLERK
 ROOKS COUNTY, KANSAS