

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 4 Twp. 10 Rge. 19 (E) (W)X

Location as "NE/CNW&SW" or footage from lines SW NW SE

Lease Owner Okmar Oil Co.

Lease Name Joy Well No. #1

Office Address 820 Union National Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 2-10-64 19

Plugging completed 2-12-64 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3713' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3400', mixed and ran 4 sacks cement thru dump bailer. Circulated hole with 19 sacks gel and spotted 20 sacks cement thru 5 1/2" casing at 470', pulled 8 joints. Spotted 20 sacks cement thru 5 1/2" casing at 180' Mudded hole to 35' and sat 5" rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
2-14-64
FEB 14 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer

Box 364, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 13 day of February, 19 64

My commission expires 24 October 1964

Sidney D. Miller
Notary Public.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- L. B. STABLEFORD
 Farm- Joy No. 1

SEC. 4 T. 10 R. 19N
 SW NW SE

Total Depth. 3711
 Comm. 11-1-53 Comp. 11-15-53
 Shot or Treated.
 Contractor.
 Issued. 1-16-54

County Rocks
 KANSAS



CASING:
 8 5/8" 208' cem w/125 sx
 5 1/2" 3707' cem w/125 sx.

Elevation. 2181

Production. Swb 9 bbls & no wtr

Figures in Parentheses Bottom of Formations.

clay	30
sand, shale	209
shale	610
shale, shells	736
sand	802
shale, stringers of sand	1036
sand	1238
shale, red bed	1247
shale, shells (sand strks.)	1500
shale, shells	1567
anhydrite	1603
shale, shells	1660
shale	2160
shale, shells lime	2312
lime, shale	2463
lime	2500
lime, shale	2592
shale, lime	2760
lime w/stringers of coarse shale, some pyrite iron	2819
lime, shale	3265
lime	3307
lime, shale	3418
lime	3513
lime, shale	3573
lime	3601
lime, shale	3635
congl. (cherty)	3662
cherty congl.	3682
congl.	3706
lime arbuckle	3711
Total Depth	

Tops: Scout.	
Heebner	3362
Lansing	3400
Conglomerate	3635
Arbuckle	3706

RECEIVED
 STATE CORPORATION COMMISSION

MAR 6 1964

CONSERVATION DIVISION
 Wichita, Kansas