

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-19416-0001

API NUMBER 8-21-51

LEASE NAME Andreson

WELL NUMBER 3

SE NW NW        Ft. from S Section Line

       Ft. from E Section Line

SEC. 4 TWP. 10 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 2-1-52 <sup>RT</sup> 8-21-51 <sup>KCL</sup>

Plugging Commenced 1-21-90

Plugging Completed 1-21-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-21-90 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed?        If not, Is well log attached?       

Producing Formation        Depth to Top        Bottom        T.D. 3771 4135

Show depth and thickness of all water, oil and gas formations. Drilled deeper 2-1-52 <sup>RT</sup> 4135' <sup>KCL</sup>

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION  
JAN 29 1990  
1-29-90  
CONSERVATION DIVISION  
Wichita, Kansas

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	180	8 5/8		
	Casing	0	3047	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each section. Perf. 1650' 4 holes 1' apart perf. 875' 4 holes 1' apart perf. 200' 4 holes 1' apart. Pump 100 sks. common down 3" cement lined tubing follow with 250 sks. 65/35 posmix, 8% gel, 1/4# flowseal per sack. Maximum pressure build up to 500#, ISP 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723 Hays, Kansas 67601 BJ Titan Cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 123 Hays, K. 67601

ROSEMARY SMITH  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXP. MAY 6 1991

26 day of January, 19 90

Rosemary Smith  
Notary Public

My Commission Expires: 5/1/1991