

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 5 Twp. 10S Rge. (X) 19 (W)

Location as "NE/CNW/SW" or footage from lines S/2 NW SE  
Lease Owner John C. Graves, et al  
Lease Name Dellett-Masters Well No. 1  
Office Address 505 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 12, 19 68  
Application for plugging filed October 12, 19 68  
Application for plugging approved October 12, 19 68  
Plugging commenced October 12, 19 68  
Plugging completed October 12, 19 68  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3460 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 800 feet. Followed by wooden plug and 1/2 sack hulls. Placed 70 sacks cement onto hulls. Mudded up with heavy mud to 240 feet followed by wooden plug, 1/2 sack hulls and 20 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10-28-68 OCT 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 68

My commission expires May 9, 1971  
Betty Braadt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves, et al  
505 Union Center  
Wichita, Kansas 67202

DRILLING COMMENCED: October 9, 1968

CONTRACTOR: Graves Drilling Co., Inc.  
505 Union Center  
Wichita, Kansas 67202

DRILLING COMPLETED: October 12, 1968

CASING RECORD: 11 Jts. 242' 8-5/8"  
cemented with 160 sacks

LOCATION: Dellett-Masters No. 1  
S/2 NW SE  
Section 5-10S-19W  
Rooks County, Kansas

-----

0 - 242	Sod & clay
242 - 1100	Shale
1100 - 1350	Sand
1350 - 1634	Red bed & shale
1634 - 1670	Anhydrite
1670 - 2090	Shale & shells
2090 - 2535	Shale & lime
2535 - 3210	Lime & shale
3210 - 3225	Shale
3225 - 3435	Lime
3435 - 3439	Shale
3439 - 3460	Lime & shale
3460	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President

STATE OF KANSAS )  
                  ) ss:  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 15th of October, 1968.

Betty Brandt  
Betty Brandt Notary Public

My commission expires May 9, 1971