

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 5 Twp. 10 Rge. 19 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW SW NW

Lease Owner C-G Drilling Co.

Lease Name Hamel Well No. 1

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-20 1954

Application for plugging filed 11-19 1954

Application for plugging approved 11-19 1954

Plugging commenced 11-20 1954

Plugging completed 11-20 1954

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production -- 19--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 840 feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	180.77	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 170'; set plug;
1/2 sack hulls, 15 sacks cement. Filled
hole with mud to 40'; set plug then filled
to top with 10 sacks cement 1/2 sack hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Vicky Jacobs (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vicky Jacobs Office Manager
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of November, 1954

Barbara Donaldson
Notary Public.

My commission expires June 17, 1957

PLUGGING
FILE SEC 5 T 10 R 19 W
BOOK PAGE 29 LINE 34

11-24-54

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. FARM NAME Hamel #1
 LOCATION SW SW NW, Sec. 5-10-19W,
 POOL NAME Berland COUNTY Rooks STATE Kansas
 COMMENCEMENT DATE November 11, 1954 COMPLETION DATE November 20, 1954

LOG OF WELL

Elevation: 2230 R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	180	Shale-Shells-Sand		
180	1360	Shale-Shells-Sand		
1360	1652	Shale-Shells-Red Bed	0° - 1500'	
1652	1684	Anhydrite		
1684	1930	Lime-Shale		
1930	2190	Lime-Shale	0° - 2000'	
2190	2415	Lime-Shale		
2415	2515	Lime-Shale	0° - 2500'	
2515	2620	Lime-Shale		
2620	2785	Lime-Shale		
2785	2885	Lime-Shale		
2885	3010	Lime-Shale	0° - 3000'	
3010	3180	Lime-Shale		
3180	3308	Lime-Shale		
3308	3400	Lime-Shale		
3400	3455	Lime-Shale		
3455	3510	Lime-Shale	0° - 3500'	
3510	3574	Lime-Shale		
3574	3632	Lime-Shale		
3632	3656	Lime-Shale		DST 3635-3656
3656	3715	Lime-Shale		
3715	3775	Lime-Shale		
3775	3805	Lime-Shale		
3805	3840	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 180.77' of 8-5/8" Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By *Wicky Jacobs*
 Office Manager

Subscribed and sworn to before me this 22nd day of November, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
 Notary Public

