

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

15-163-02614-0000
 RECEIVED Form CP-4
 STATE CORPORATION COMMISSION
 Rev. 12-15-80
 9-27-82
 SEP 27 1982

WELL PLUGGING RECORD

CONSERVATION DIVISION
 Wichita, Kansas

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 5 TWP. 10S RGE. 19W E/W
 Location as in quarters or footage from lines:
SE NW NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Tomlinson Oil Co
 Lease Name Hamel Well No. 3
 Office Address 200 W Douglas, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Disposal
 Date Well Completed 9-62
 Application for plugging filed 8-31-82
 Plugging commenced 9-21-82
 Plugging completed 9-21-82
 Reason for abandonment of well or producing formation uneconomical

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation Granite Depth to top 3863 bottom 4141 T.D. 4141
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	168'	none
				5 1/2"	3863'	"

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Hooked onto 5 1/2" casing & pumped 2 sxs hulls,
200 sxs 50/50 Poz 6% gell 3% CC with 1 sx hulls in first part of cement,
pressure to 500#, shutdown for 2 hrs, mixed & pumped 60 sxs 50/50 Poz 6% gel
3% CC & shutdown for 3 hrs, mixed 30 sxs 50/50 Poz 6% gel 3% CC with 1 sx
hulls, pressured to 300# held.
Hooked onto Braden Head & pressured between 8 5/8" & 5 1/2" to 300# held.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor none

STATE OF Kansas COUNTY OF Barton, ss.

Stanley Freeman (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Stanley Freeman
 3120 Meadowlark, Gt. Bend, Kansas
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of Sept, 19 82

Rita Baker
 Notary Public.

My Commission expires: 4-30-83



15-163-02614-0000

ORIGINAL

STENCILED

NOV 17 1963

5-10-19W
S2 NW NW

DRILLERS LOG
TOMLINSON-KATHOL, INC.
3 HAMEL
SE NW NW, Sec. 5-10S-19W
ROOKS COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 8/7/62
Completed: 8/18/62
Elevation: 2215' KB
Prod. SWDW

From	To	Description	Remarks
0	70	Clay & Sand	
70	166	Shale & Sand	168' 8-5/8" Surf. Csg. w/125 sacks cement
166	1400	Shale	
1400	1635	Sand & Shale	5 1/2" @ 3863'
1630	1652	Anhydrite	
1652	2005	Shale	
2105	2464	Shale - Lime	
2465	2864	Lime - Shale	
2864	2940	Shale & Lime	
2940	3125	Lime, Shale	
3125	3373	Shale - Lime	
3373	3731	Lime	Loss:
3731	3806	Conglomerate	Heebner 3427
3806	4141	Arbuckle	Lansing 3465
		TA	Cong. Sh. 3703
			Cong. Chert 3730
			Arbuckle 3798
			5 1/2" Casing 3863'

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

Richard C. Davis
Richard C. Davis

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 21st day of August, 1962.

Esther Lamone
Esther Lamone, Notary Public

My Commission Expires: 1/19/65

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1962
CONSERVATION DIVISION
Wichita, Kansas