

15-163-01893-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
9-27-82 Rev. 12-15-80  
SEP 27 1982  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rooks SEC. 5 TWP. 10S RGE 19W E/W  
Location as in quarters or footage from lines:  
NW SE NW


Lease Owner Tomlinson Oil Co  
Lease Name Hamel Well No. 4  
Office Address 200 W Douglas, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): oil  
Date Well Completed 9-62  
Application for plugging filed 8-31-82  
Plugging commenced 9-21-82  
Plugging completed 9-21-82  
Reason for abandonment of well or producing formation  
low production & hole in casing  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Locate Well  
correctly on above  
Section Platt.

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
Producing formation Arbuckle Depth to top 3767' bottom 3771' T.D. 3771'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	164'	none
				5 1/2"	3768'	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Ran tubing down 5 1/2" & spotted 12 sxs 50/50 Poz 6% gel 3% CC, pulled tubing & let set 3 hrs, hooked onto 5 1/2" & pumped 2 sxs hulls & 140 sxs 50/50 Poz 6% gel 3% CC with 1 sx hulls in first part of cement, filled & squeezed at 800#  
Hooked onto Braden Head & cemented between 8 5/8 & 5 1/2 with 2 sxs hulls & 120 sxs 50/50 Poz 6% gel 3% CC & squeezed at 400# held. Completed at 6:30 PM

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor none

STATE OF Kansas COUNTY OF Barton, ss.  
Stanley Freeman (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley Freeman  
3120 Meadowlark, GT. Bend, Kansas  
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of Sept, 1982

Rita Baker  
Notary Public.

My Commission expires:



