

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01895-0000

API NUMBER N/A

LEASE NAME GISH

WELL NUMBER 2

330 Ft. from S Section Line

~~4290~~ ~~1650~~ Ft. from E Section Line

^{PT} SEC. 6 TWP. 10S RGE. 19 (X) or (W)

COUNTY Rooks

Date Well Completed 12-23-50

Plugging Commenced 9-22-92

Plugging Completed 9-22-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-21-92 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Lansing Depth to Top 3623 Bottom 3627 T.D. 3785

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil & Water	3471	3722	8-5/8	210	-
Arbuckle	Water	3783	3785	5-1/2	3781	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 3 sks hulls followed by 275 sks cement and filled 5-1/2 casing full of cement from 0 to 3623 ft. Hooked on to 5-1/2 x 8-5/8 annulus & pumped 1 sk hulls followed by 50 sks cement. Shut-in w/300 psi. Cut off & restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cement License No. N/A

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Joseph G. Anderson, Chief Engineer

(Employee of Operator) Wichita, Kansas of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joseph Anderson

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 92

Kathy Barrow
Notary Public

My Commission Expires: 8-1-95

RECEIVED
STATE CORPORATION COMMISSION
10-13-92
OCT 13 1992

CONSERVATION DIVISION
Wichita, Kansas

NADRL AND GUSMAN

GISH No. 2

990' E. 330' W. of SWc
Section 6-108-19W
Rooks County, Kansas

Comm. 12-15-50
Comp. 12-23-50

Casing: 8-5/8" 160' w/125 sax cement
5-1/2" 3785.75' w/100 sax cem

Formation	Depth
Surface	160
Shale	810
Shale-sand	1100
Sand	1330
Shale and shells	1615
Shale and Red bed	1650
Anhydrite	1689
Shale and Red beds	1790
Shale and shells	2275
Shale and lime shells	2330
Broken lime	2420
Shale and lime	2650
Shale and lime shells	2820
Shale and lime	3500
Lime	3695
Shale	3708
Shale - chert	3758
Shale	3771
Shale and sand	3783A
Arbuckle Lime	3785 T.D.

Geological Tops

Hoebner	3434
Toronto	3454
Lansing	3471
Conglomerate	3722
Simpson	3771
Arbuckle	3783

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

L. G. Hay of lawful age, deposes and states that the above formations and depths are correct as taken from the daily drilling report of the Gish No. 2 well located in the SW corner of Section 6-108-19W, Rooks County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1950

Subscribed and sworn to before me this 27th day of December, 1950.

Walter B. [Signature]
Wichita, Kansas
Notary Public

My commission expires Nov. 3, 1952