

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-03221-0000

API NUMBER N/A

LEASE NAME PYWELL

WELL NUMBER 1A

SPOT LOCATION NE NW SW

SEC. 6 TWP. 10 RGE. 19 ~~19~~ (NW)

COUNTY Rooks

Date Well Completed 6/3/57

Plugging Commenced 10/2/85

Plugging Completed 10/2/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - Hays, Kansas

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3786 bottom 3790 T.D. 3790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil (depleted)	3786	90	8-5/8	182	none
				5-1/2	3785	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1 sack hulls, 25 sacks 60/40 Poz, 7 sacks gel; then 215 sacks 60/40 Poz down 5 1/2" casing; SIP 250#; 20 sacks 60/40 Poz down 8-5/8" - 5 1/2" annulus; SIP 500#
Witnessed by state plugger: Dennis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____

Address Box 13 - Russell, Kansas 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) MR Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 85

My Commission expires: 5/11/87

RECEIVED
STATE CORPORATION COMMISSION Public
10-10-85
OCT 9 0 1985

Well Log

Nadel and Gussman

Pywell Well A-1

NE NW SW 6-10-19W
Rooks County, Kansas

Comm: 5-24-57
Comp: 6-3-57

Casing: 8-5/8" 182' w/135 sax
5-1/2" 3785' w/75 sax

Formations

Depth

Shale, sand and shale	182
Shale and shells	810
Sand	940
Shale and shells	1130
Sand	1420
Shale, shells and red beds	1660
Anhydrite	1700
Shale and shells	2100
Shale and lime	2800
Lime	2890
Lime and shale	3135
Lime	3210
Lime and shale	3355
Lime	3680
Lime and chert	3755
Lime and shale	3774
Lime	3790

GEOLOGICAL TOPS

Heebner	3436'
Toronto	3454'
Lansing	3474'
Base Kansas City	3686'
Conglomerate Chert	3712'
Simpson Shale	3756'
Arbuckle	3786'

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

L. C. Hay

Subscribed and sworn to before me this 5th day of June, 1957.

[Signature]
Notary Public

My commission expires Nov. 3, 1960

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 0 1955

CONSERVATION DIVISION
Wichita, Kansas