



WELL LOG  
Sinclair Oil & Gas Co

Charles Pywell # 1  
N/2 SW/4, 6-10S-19W, Rooks Co.  
330' fm Sth & 990' fm East  
Elev. 2232 rig floor

Harbar Drilling Co., rotary  
Spudded 6PM 4/1/1950  
Completed drlg 4/16/1950  
T.D. 3970'  
Ran Schlumberger  
Dry Hole  
Plugged & abandoned 4/18/1950

Drillers Log  
Surface Level Measurements  
Add 2' for rig floor meas,

Sand & Shale	235'
Shale	295
Set 10-3/4" @ 295' w/200sx	
Shale & Shells	1235
Shale & Sand	1455
Shale & Shells	1680
Shale & Gravel	1775
Shale	2155
Lime & Shale	2630
Shale & Lime	2785
Lime & Shale	2875
Shale & Lime	3000
Lime & Shale	3185
Shale	3230
Lime & Shale	3360
Shale & Lime	3405
Lime & Shale	3500
Cherty Lime	3505
Lime & Shale	3570
Lime	3625
Cherty Lime & Shale	3665
Shale & Lime	3685
Lime	3715
Conglomerate	3800
Shale & Lime	3854
Cherty Lime & Shale	3895
Lime & Shale	3900
Chert	3930
Cherty Lime & Shale	3950
Lime	3970 TD

Geological Tops;

Topeka	3249'
Hebener Shale	3455
Lansing	3494
Conglomerate	3735
Arbuckle	3933

