

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

ROOKS

County. Sec. 6 Twp. 10 Rge. 19W (EX) (W)

Location as "NE/CNW&SW&" or footage from lines NE SW NE

Lease Owner Nedel and Gussman

Lease Name Gish Well No. 6

Office Address 1714 First National Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 12-16-55

Application for plugging filed 12-16-55

Application for plugging approved 12-16-55

Plugging commenced 12-16-55

Plugging completed 12-16-55

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3847 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	165	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from T.D. to 160'

Set plug at 160' with 15 sax cement

Filled hole to 40' of top with mud

set plug at 40' with 10 sax cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Reserve Drilling Company, Inc.

Address 703 Union National Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. C. Hay (employee of owner) ~~OR OWNER OR OPERATOR~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) L. C. Hay

Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 55

Noia Babb
Notary Public.

My commission expires Nov. 3, 1956



WELL LOG

Nadel and Gussman

GISH No. 6

NE SW NE G-10-19W
Rooks County, Kansas

Comm: 12-7-55
Comp: 12-16-55

Casing: 8-5/8" 165' with 150 sax

Sand and shale	220
Shale and shells	875
Sand	915
Shale	1115
Sand	1335
Shale and red bed	1655
Anhydrite	1693
Shale and shells	2285
Shale and lime	3445
Lime	3745
Conglomerate	3800
Cherty Conglomerate	3847

Geological Tops

Water	3452
Toronto Lime	3474
Lensing-Kansas C.	3492
Base Kansas City	3703
Chert Conglomerate	3820

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, states that the above tops, formations and depths are correct as shown by the daily drilling log of the Gish No. 6 in the NE SW NE of G-10-19W, Rooks County, Kansas.

L. C. Hay

L. C. Hay

Subscribed and sworn to before me this 20th day of Dec. 1955.

Noel Babb

Noel Babb, Notary Public

My commission expires Nov. 3, 1956

INDEXED
SER 2 6 10 19W
INDEX PAGE 26 SERIAL 14