


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Rooks County. Sec. 6 Twp. 10 Rge. 19 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
S/2 NW NW

Lease Owner F & M Oil Co., Inc.
Lease Name Childs Well No. 1
Office Address 505 Union Center, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed Oct. 11, 19 76
Application for plugging filed Oct. 11 19 76
Application for plugging approved Oct. 11 19 76
Plugging commenced Oct. 11 19 76
Plugging completed October 11 19 76
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3840
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud. Bottom plug at 720' with 70 sacks 50/50 Poz, 6% Gel-thru drill pipe
Middle Plug @ 240' with 20 sacks cement thru drill pipe
Top plug @ 40' - $\frac{1}{2}$ sack hulls & 10 sacks cement.
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
10-13-76
OCT 13 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.
Box 823 - Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or ~~owner or operator~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 76

Dorothy M. Hague
Notary Public.

My commission expires April 11, 1978

Drillers' Well Log

Date Commenced: October 4, 1976
 Date Completed: October 11, 1976

J & M Oil Co., Inc.
 CHOLDS #1
 S/2 NW NW
 Sec 6 - Twp 10, Rge 19N
 Roake County, Kansas

Elevation: 2233 H.B.

- 0 - 80' Clay
- 80' - 250' Shale, Sand Streaks
- 250 - 1330' Shale, Red Bed, Sand
- 1330 - 1652' Shale & Sand Streaks
- 1652 - 1687' Anhydrite
- 1687 - 3235' Shale & Lime
- 3235 - 3444' Lime
- 3444 - 3449' Shale
- 3449 - 3487' Shale & Lime
- 3487 - 3698' Lime
- 3698 - 3748' Lime & Shale
- 3748 - 3815' Chert, Shale
- 3815 - 3840' Dolomite

Formation Tops

Anhydrite	1652
Jopoka	3235
Heabner	3444
Lansing	3487
Base K.C.	3698
Cherty Congl.	3748
Rebuckite	3815
RJD	3840

Surface Pipes: Set 250' of
 160 sacks of common cement,
 2 gal and 3/8 cc.

A J J O D A V O J

State of Kansas
 (County of Barton) ss.

Larry Curtis of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 11 day of October 1976

By Commission Expires
 April 11, 1978

Verdya M. Hogue
 Notary Public

RECEIVED
 OCT 13 1976
 COMMISSION