

15-205-19453-00-00

3 023106

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20070001-01
NW,NW,NE 1/4 Sec/Twp/Rge S.3-T.27S.-R16E.
5203 feet from south section line
2578 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 100101
Operator: STATE OF KANSAS
Name & BUFFALO III FEE FUND
Address PLUGGING PROJECT

Lease/Well# FOSTER ~~NO. 2~~ FOS01
County WILSON
Well Total Depth 950' feet
Production Pipe: 2" Size Feet 950'
Surface Casing: 8" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well D & A
Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372
Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00AM Day: _____ Month: 10 2006

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT
HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO
CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All Part None

Operations Completed: Hour: 01:00PM Day: _____ Month: 10 2006

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT
SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS
TO 550'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM
THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT
WAS FILLED FROM SURFACE. 172 SACKS WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.01) (THIS WAS WELL WAS NO. 2 ON THE OLD LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED

NOV 08 2006

KCC WICHITA