

3 023138

15-205-19439-00-00 Correction 4-16-07

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER SW NE NE CONTROL NO. 20070001-010
NE SW 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.
* 4032 3638 feet from south section line
* 7461 1733 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 100701
Operator: STATE OF KANSAS
Name & BUFFALO III FEE FUND
Address PLUGGING PROJECT
AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Lease/Well# FOSTER NO.10-I
County WILSON
Well Total Depth 950' feet
Production Pipe: 2 Size Feet 950'
Surface Casing: 6" Size Feet 20'
E-4207 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372
Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00 A.M. Day: _____ ☿ Month: 3 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTS OF 2" CASING TO APPROXIMATELY 950' THAT HAS BEEN CEMENTED IN FROM BOTTOM TO APPROXIMATELY 200'. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All X Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 1:00P.M. Day: _____ ☿ Month: 3 2007

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 6" ANNULUS TO 200. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 6" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 73 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.10) (THIS WAS WELL NO.10-I ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: _____

Clayton P. Titel
RECEIVED
KANSAS CORPORATION COMMISSION

APR 13 2007

CONSERVATION DIVISION
WICHITA, KS

15-205-19439-00-00

3-19-07

3 023138

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20070001-010
NE,SW,NE 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.
3638 feet from south section line
1733 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101

Lease/Well# FOSTER NO.10-I

Operator: STATE OF KANSAS

County WILSON

Name & BUFFALO III FEE FUND

Well Total Depth 950' feet

Address PLUGGING PROJECT

Production Pipe: 2 Size Feet 950'

AB oil well Gas Well SWD Well/ Input Well

Surface Casing: 6" Size Feet 20'

E-4207 D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00 A.M. Day: 3 Month: 3 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTS OF 2" CASING TO APPROXIMATELY 950' THAT HAS BEEN
CEMENTED IN FROM BOTTOM TO APPROXIMATELY 200'. THE PLUGGING PROPOSAL WAS
TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN
None

Operations Completed: Hour: 1:00P.M. Day: 3 Month: 3 2007

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 6"

ANNULUS TO 200. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 6" SURFACE CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

73 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.10) (THIS WAS WELL NO.10-i ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel

TECHNICIAN RECEIVED
KANSAS CORPORATION COMMISSION

MAR 16 2007

CONSERVATION DIVISION
WICHITA, KS