

15-205-19456-00-00

3 023115

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20070001-024
SW,SE,NE 1/4 Sec/Twp/Rge S.3-T.27S.-R16E.
2721 feet from south section line
934 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 100 101
Operator: STATE OF KANSAS
Name & BUFFALO III FEE FUND
Address PLUGGING PROJECT

Lease/Well# FOSTER NO.2-I-C
County WILSON
Well Total Depth 950' feet
Production Pipe: 2" Size Feet 950'
Surface Casing: 8" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well D & A
Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372
Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00AM Day: _____ Month: 11 2006
Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT
HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO
CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All Part _____ None _____

Operations Completed: Hour: 2:30P.M. Day: _____ Month: 11 2006

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT
SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS
TO 525'. AT THAT DEPTH, SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS PUMPED
INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE.
THE 1" PIPE WAS REMOVED. 140 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.24) (THIS WELL WAS NO. 2-I-C ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
NOV 20 2006
KCC WICHITA