

3 023291

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19547-00-00
CONTROL NO. 20070001-006
NW,NW,NE 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.
4682 feet from south section line
2028 feet from east section line

8

TECHNICIAN'S PLUGGING REPORT
Operator License # 100101
Operator: STATE OF KANSAS
Name & BUFFALO III FEE FUND
Address PLUGGING PROJECT

Lease/Well# FOSTER NO. 4-I
County WILSON
Well Total Depth 950' feet
Production Pipe: 2" Size Feet 950'
Surface Casing: 6" Size Feet 20'

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-4702 D & A _____
Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372
Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00:AM Day: 14 Month: 2 2008
Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO 220'. THE PLUGGING PROPOSAL WAS CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

RECEIVED KANSAS CORPORATION COMMISSION

FEB 22 2008

CONSERVATION DIVISION WICHITA, KS

Plugging Proposal Received by: CLAYTON P. TITEL TECHNICIAN
Plugging attended by Agent: All _____ Part X None _____

Operations Completed: Hour: 4:00P.M. Day: 14 Month: 2 2008

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 900'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" PIPE AT SUFRACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 6" ANNULUS TO 220'. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS PMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.DISPLACEMENT WAS FILLED FROM SURFACE. 78 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.6) (THIS WELL WAS NO. 4-I ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

PCT