

3 023287

15-205-19552-00-00

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20070001-056  
NW,NE,NE 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.  
5015 feet from south section line  
1010 feet from east section line



TECHNICIAN'S PLUGGING REPORT  
Operator License # 100101  
Operator: STATE OF KANSAS  
Name & BUFFALO III FEE FUND  
Address PLUGGING PROJECT

Lease/Well# FOSTER NO.2 P  
County WILSON  
Well Total Depth 950' feet  
Production Pipe: 2" Size Feet 950'  
Surface Casing: 6" Size Feet 20'

AB oil well  Gas Well  SWD Well/ Input Well  D & A

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372  
Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00:AM Day: \_\_\_\_\_ 7 Month: 2 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO 215'. THE PLUGGING PROPOSAL WAS CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

RECEIVED KANSAS CORPORATION COMMISSION

FEB 22 2008

Plugging Proposal Received by: CLAYTON P. TITEL TECHNICIAN  
Plugging attended by Agent: All  Part  None

CONSERVATION DIVISION WICHITA, KS

Operations Completed: Hour: 12:00P.M. Day: \_\_\_\_\_ 7 Month: 2 2008

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" PIPE AT SUFRACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 6" ANNULUS TO 215'. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS PMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.DISPLACEMENT WAS FILLED FROM SURFACE. 78 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.33) ( THIS WELL WAS NO. 2-P ON THE LEASE MAP. )  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel TECHNICIAN

PKT