

3 023362

15-205-19566-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20070031-006
NE,NE,SE 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.
2321 feet from south section line
356 feet from east section line

0

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101

Lease/Well# GLAMSER NO.3-P

County WILSON

Operator: STATE OF KANSAS

Well Total Depth 950' feet

Name & BUFFALO IV FEE FUND

Production Pipe: 2" Size Feet 950'

Address PLUGGING PROJECT

Surface Casing: 6" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 21 Month: 4 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO 400'. THE PLUGGING PROPOSAL WAS CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ None X

Operations Completed: Hour: 1:00P.M. Day: _____ 21 Month: 4 2008

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 900'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SUFRACTE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 6"

ANNULUS TO 400'. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT

SURFACE. THE 1" PIPE WAS REMOVED.DISPLACEMENT WAS FILLED FROM SURFACE.

93 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.6) (THIS WELL WAS NO. 3-P ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 19 2008

CONSERVATION DIVISION
WICHITA, KS

I DID NOT observe this plugging.

Signed: Clayton Titel
TECHNICIAN

per
PRT
PRT