

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20871-00-00
Spot: NENE Sec/Twnshp/Rge: 35-29S-40W
4500 feet from S Section Line, 607 feet from E Section Line
Lease Name: KAYLEE BROOKE Well #: 1-35
County: STANTON Total Vertical Depth: 5750 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5325		WITH 2 SX CMT
SURF	8.625	1792		WITH 870 SX CMT
DVT		2901		WITH 435 SX CMT 186.88
PROD	4.5	5708	0	WITH 435 SX CMT

Well Type: OIL UIC Docket No: 34069 Date/Time to Plug: 05/21/2009 8:00 AM
Plug Co. License No.: 32453 Plug Co. Name: BASIC ENERGY SERVICES, LP KCCPT
Proposal Rcvd. from: CLINT ANDREWS Company: PRESCO WESTERN Phone: (303) 444-8881

Proposed Plugging Method: TAG RBP # 5,500' & DUMP 25 SX CMT. PU, SPOT 20 SX CMT @ 3,850'. SPOT 25 SX CMT @ 2950' (DV TOOL@2902') PU, SPOT 20 SX CMT @ 1815' (8 5/8" CSG SHOE @ 1792') PU. SPOT 60 SKS CMT @ 600' TO SURFACE IN 4 1/2" CSG. DUMP 15 SKS DOWN BACKSIDE OF SURFACE CSG. VERBAL AGREEMENT BETWEEN KEN JEHLIK OF THE KCC & RANDY VERRET OF PRESCO WESTERN ON 5/19/2009

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2009 2:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

1ST PLUG CIBP @ 5325' WITH 2 SX CMT. 2ND PLUG AT 3850' WITH 20 SX CMT. 3RD PLUG AT 2950' WITH 20 SX CMT. 4TH PLUG AT 1850' WITH 20 SX CMT. 5TH PLUG AT 650' WITH 70 SX CMT. FILLED TO SURFACE. PUMPED 18 SX CMT DOWN BACKSIDE. PRESSURED TO 400 PSI.

Perfs:

Top	Bot	Thru	Comments
5596	5612		

INVOICED
DATE 8/17/09
INV. NO. 2010060101

KANSAS CORPORATION COMMISSION
JUN 17 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
JUN - 9 2009
KCC DODGE CITY

Signed Jack Macclashy
(TECHNICIAN)
Form CP-2