

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20433-00-01
Spot: NESWSE Sec/Twnshp/Rge: 21-8S-18W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HARMONY HILL UNIT Well #: 303W
County: ROOKS Total Vertical Depth: 3451 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	195	0	w/130 sxs cmt
T1	2.375	2984		
DVT		1296		112.16
PKR		2984		
PROD	4.5	3449	0	w/115 sxs cmt

Well Type: EOR UIC Docket No: E23203.1 Date/Time to Plug: 06/05/2009 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV tool at 1296' w/250 sxs. Casing leak at 2800'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2009 11:15 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 225 sxs 60/40 pozmix - 4% gel with 500# hulls down 4 1/2" casing.
Shut in 30 minutes.
Hooked up to backside - pumped 50 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.
Topped 4 1/2" casing with 35 sxs cement - casing full.

Perfs:

Top	Bot	Thru	Comments
3127	3416		

INVOICED
DATE 8-17-09
INV. NO. 2010060109

RECEIVED
JUN 15 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed R. Edward Williams
(TECHNICIAN)

CM PKT

CITIES SERVICE OIL
& GAS CORPORATION
800 SUTTON PLACE #303 HARMONY HILL UNIT "OWWO" 21-8-18W
WICHITA, KS 67202 NE SW SE

CONTR REVLIN DRILLING, INC. CTY ROOKS

GEOL _____ FIELD HARMONY HILL

ELV 1976 KB SPD 4/19/84 CARD ISSUED 10/11/84 IP WIW
1977 GL
API 15-163-20.433-A SHAW(TOP) 3127-3130
LKC 3148-3368 OA
ARB 3406-3416

LOG	Tops	Depth/Datum
SC		1355 + 621
HEEB		3104-1128
LANS		3148-1172
BKC		3371-1395
ARB		3401-1425
RTD		3451-1475

OLD INFO: OPERATOR WAS NATIONAL OIL COMPANY, #3
MOSHER, SPD 4/20/72, SET 8 5/8 " 198, COMP AS D & A / ARB,
4/29/72, (CARD ISSUED 5/11/72), CONTR: B & B DRILLING
DST (1) 3137-3155 (LKC) / 15-30-60-30, REC 1170" MW, SIP
1066-1009#, FP 35-598#
DST (2) 3197-3215 (LKC) / 15-30-15-30, REC 5' MUD, SIP
1066-1009#, FP 35-35#
DST (3) 3225-3235 (LKC) / 15-30-60-30, REC 950' MW, SIP
985-892#, FP 35-528#
DST (4) 3267-3330 (LKC) / 15-30-60-30, REC 1' OIL, 70" THIN
MUD, SIP 1123-1066#, FP 46-70#
DST (5) 3328-3370 (LKC) / 15-30-45-30, REC 10' MUD, SIP
845-939#, FP 46-46#
DST (6) 3368-3410 (LKC, ARB) / 30-30-30-30, REC 40' OIL SPTD
MUD, SIP 892-140#, FP 35-46#
(over)

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

CITIES SERVICE OIL
& GAS CORPORATION #303 HARMONY HILL UNIT "OWWO" 21-8-18W
NE SW SE

NEW INFO: FR 4/17/84, RE-ENTERED 4/19/84, WSH DWN TO 3450 TD, SET 4 1/2 " 3449 / 115SX, SET DV TOOL
AT 1296 / 250SX, MICT - CO, PF (ARB) 3406-16 & (LKC) 3362-68, 3341-45, 3316-26, 3241-48, 3229-35,
3220-30, 3148-52 & (TOR) 3127-30, W/ 4 SPF, AC 3000G (15%), SWB DWN, SET 2" TBG AT 3092, WIW, IN-
JECTION RATE SATISFACTORY