

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21360-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 19-28S-17W  
4678 feet from S Section Line, 3407 feet from E Section Line  
Lease Name: E WYNONA ROSS Well #: 1  
County: KIOWA Total Vertical Depth: 4940 feet

Operator License No.: 6926  
Op Name: ADVANTAGE RESOURCES, INC.  
Address: 1775 SHERMAN ST STE 1700  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	482		WITH 280 SX CMT
DVT		1128		WITH 300 SX CMT
PROD	4.5	4943	0	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2009 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: LARRY MITCHELL Company: ADVANTAGE RESOURCES Phone: (620) 546-3649

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. RUN TBG TO 1130' & FILL 4 1/2" CASING WITH CMT TO 0'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/01/2009 12:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 100# HULLS - 25 SX CMT. CMT DISPLACED TO 4700'. RAN TBG TO 1130'. CIRCULATED CMT UP 4 1/2" WITH 70 SX CMT TO SURFACE. PULLED TBG. TOPPED OFF 4 1/2" WITH 7 SX CMT. PUMPED 50 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS @ 250 PSIG. CMT SURFACED 4' FROM WELLHEAD.

Perfs:

Top	Bot	Thru	Comments
4808	4814		

INVOICED  
DATE 8-31-09  
INV. NO. 2010060162

KANSAS CORPORATION COMMISSION

JUL 31 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

JUL 14 2009

KCC DODGE CITY

Form CP-2