

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05425-00-00
Spot: NENESE Sec/Twnshp/Rge: 9-19S-2W
2142 feet from S Section Line, 604 feet from E Section Line
Lease Name: SEVERTSON Well #: 1
County: MCPHERSON Total Vertical Depth: 2975 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	125		NO SXS LISTED
PROD 5		2969		NO SXS LISTED 96.69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2009 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: JAKE SIGEL Company: AMERICAN ENERGIES Phone: (316) 263-5785

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 4 SXS CEMENT. CIRCULATE WITH CEMENT FROM 450' TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 06/29/2009 2:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

HOLE WAS PLUGGED (BRIDGED) OFF AT 1900'. DRILLED DOWN TO 2762'.
CAPPED WITH 4 SXS CEMENT. CUT CASING AT 519' AND PULLED. RAN TUBING
TO 450' AND PUMPED 275 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2950	2957		

INVOICED
DATE 8-31-09
INV. NO. 2010060163

KANSAS CORPORATION COMMISSION
JUL 16 2009
RECEIVED

Remarks: GRESSEL OILFIELD SERVICES TICKET #35316 TOTAL = 275 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

JK

PST