

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00190-00-00
Spot: SE Sec/Twnshp/Rge: 11-23S-38W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: MILES C Well #: 1
County: KEARNY Total Vertical Depth: 2748 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	843		WITH 500 SX CMT
PROD	5.5	2747	0	WITH 1000 SX CMT 89.31

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/25/2009 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2009 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 5 1/2" CASING W/CMT FROM 2734-0' IN 2 STAGES. 1ST STAGE: PUMP 200# HULLS & 150 SX CMT DOWN THE 5 1/2" CASING. LET SET FOR 45 MINUTES. 2ND STAGE: PUMP 118 SX CMT DOWN 5 1/2" CASING. PRESSURED TO 400# & HELD. PUMPED 2 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2729	2734		
2702	2706		
2686	2698		
2660	2666		
2644	2652		
2636	2640		

INVOICED
DATE 8-31-09
INV. NO. 2010060108

KANSAS CORPORATION COMMISSION

JUL 27 2009

RECEIVED

Remarks: USED CLASS C CMT & 2% GEL BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

JUL - 7 2009

KCC DODGE CITY

Form CP-2/3

PPA