

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01805-00-01
Spot: E2SWSW Sec/Twnshp/Rge: 34-21S-13W
707 feet from S Section Line, 4347 feet from E Section Line
Lease Name: GATES Well #: 2
County: STAFFORD Total Vertical Depth: 3743 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 298 | | |
| PROD | 5.5 | 3720 | 0 | 121.65 |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2009 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2009 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****SQUEEZED @ 500' WITH 300 SX CMT. SQUEEZED @ 3000' WITH 200 SX CMT.****
RAN TBG & STACKED OUT @ 3240'. PUMPED 15 SX GEL- 150# HULLS - 50 SX CMT.
PULLED TBG TO 750' & CIRCULATED CMT TO SURFACE WITH 90 SX CMT.
PULLED TBG & TOPPED OFF 5 1/2" WITH 15 SX CMT. PRESSURED 8 5/8" X 5 1/2"
WITH CMT TO 800 PSIG. BLEW UP HEAD. NO ENTRY.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3720 | 3743 | OH | |
| 3543 | 3552 | | |
| 3518 | 3526 | | |
| 3501 | 3505 | | |
| 3485 | 3490 | | |
| 3432 | 3436 | | |
| 3386 | 3392 | | |

RECEIVED
JUL 13 2009
KCC WICHITA
INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

DATE 8-31-09
INV. NO. 2010060171

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
JUN 30 2009
KCC DODGE CITY

Form CP 2/3
[Handwritten initials]