

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01747-00-00
Spot: SWNENW Sec/Twnshp/Rge: 30-18S-7W
4302 feet from S Section Line, 3778 feet from E Section Line
Lease Name: SAM AINSWORTH Well #: 6
County: RICE Total Vertical Depth: 3183 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	6	3100		CEMENT RETAINER AT 3170'
SURF	10.75	203		125 SX
PROD	6	3180		250 SX 103.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2009 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2009 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1050', 700', AND 260'. RUN TUBING TO 3070' AND PUMP 100 SX'S CEMENT WITH 300#'S COTTON HULLS. PULL TUBING TO 1050' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 700' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 260' AND CIRCULATE CEMENT TO SURFACE. PUMP CEMENT ON BACKSIDE OF 6" AT 300#'S. PULL TUBING OUT AND TOP OFF. USED 295 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
3145	3152	CSG	
2932	2936	CSG	
2777	2782	CSG	

INVOICED
DATE 8-31-09
INV. NO. 2010060174

KANSAS CORPORATION COMMISSION

JUL 16 2009

RECEIVED

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #5764. COPELAND TICKET #C-35323

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

PKT