

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20118-00-00
Spot: NE Sec/Twnshp/Rge: 19-19S-31W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: YAGER Well #: 1-19
County: SCOTT Total Vertical Depth: 2792 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2550		WITH 2 SX CMT
SURF	8.625	367		WITH 265 SX CMT <u>90.74</u>
PROD	4.5	2790	0	WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/26/2009 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: EDDIE AMBERCROMBIE Company: FIML NATURAL RESOURCES Phone: (620) 793-2816

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2009 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

2 3/8" TBG FISH @ 2746'. SQUEEZED CASING LEAKS @ 1870-1902' WITH 500 SX CMT. CIBP @ 2550' WITH 2 SX CMT. LOAD HOLE WITH WATER. RAN BOND LOG FROM 2550' - 0'. TOC @ 120'. RAN TBG TO 1561'. CIRCULATE CASING FULL OF CMT TO SURFACE. TOOH W/TBG. TOP OFF WITH CMT. A TOTAL OF 135 SX CMT DOWN CASING. STAYED FULL. PUMP 12 SX CMT DOWN ANNULUS TO 300 PSI. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2574	2766		

INVOICED
DATE 8-31-09
INV. NO. 2010060180

KANSAS CORPORATION COMMISSION
JUL 27 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)

RECEIVED
JUL - 6 2009
KCC DODGE CITY