

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20538-00-00
Spot: SESE Sec/Twnshp/Rge: 7-19S-31W
500 feet from S Section Line, 400 feet from E Section Line
Lease Name: DEARDEN Well #: 1-7
County: SCOTT Total Vertical Depth: 4712 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		WITH 160 SX CMT
DVT		2254		WITH 200 SX CMT
PROD	4.5	2964	0	WITH 115 SX CMT <u>153.14</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/24/2009 1:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: EDDIE AMBERCROMBIE Company: FIML NATURAL RESOURCES Phone: (620) 793-2816

Proposed Plugging Method: PUMP 200# HULLS & 175 SX CMT. 50 SX CMT DOWN ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2009 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2804' TO 0' USING 180 SX CMT & 200# HULLS. PRESSURE TO 500# & HELD. PUMP 15 SX CMT DOWN ANNULUS TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
2776	2784		KRIDER

INVOICED
DATE 8/31/09
INV. NO. 2010060180
KANSAS CORPORATION COMMISSION
JUL 27 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Ken Jehlik (TECHNICIAN)

RECEIVED
JUL - 6 2009
KCC DODGE CITY