

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21532-00-00
Spot: SENENWNE Sec/Twnshp/Rge: 34-34S-20W
495 feet from N Section Line, 1485 feet from E Section Line
Lease Name: KUHNS Well #: 4
County: COMANCHE Total Vertical Depth: 201 feet

Operator License No.: 33513
Op Name: FIVE STAR ENERGY, INC.
Address: 215 E 14TH ST
HARPER, KS 67058

String Size Depth (ft) Pulled (ft) Comments
COND 60 10

35 -

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 05/20/2009 12:05 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JEFF BURKE Company: FIVE STAR ENERGY Phone: (620) 896-2710

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2009 3:27 PM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

Perfs:

PLUGGING WITNESSED BY ERIC MACLAREN ON 5/20/09, JERRY STAPLETON ON 5/21/09, & LIN REIMER ON 5/22/09. 1ST PLUG DRILLED DOWN TO 190'. LOST CIRCULATION. PULLED DRILL PIPE & WORKED ON SURFACE LOCATION. SDFN. 2ND PLUG DRILLED DOWN TO 190' KB-STUCK D.P. PUMPED 350 SX 60/40 POZMIX 4% GEL. NO RETURNS, ON SLIGHT VACUUM. PULLED OUT D.P.. SDFN. 3RD PLUG TAGGED CMT @ 145' WITH D.P. PUMPED 400 SX CMT. DID NOT CIRCULATE. 4TH PLUG WAIT ON CMT 3.5 HOURS. TAGGED CMT @ 110'. PUMPED 200 SX COMMON W/3% CC. CMT CIRCULATED TO SURFACE.

INVOICED
DATE 8/31/09
INV. NO. 2010060181

RECEIVED
JUL 13 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL & COMMON W/3% CC BY ALLIED.

Plugged through: DP

District: 01

Signed _____

[Signature]
(TECHNICIAN) *[Signature]*

RECEIVED

JUL -7 2009

KCC DODGE CITY

Form *[Signature]*