

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-22174-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 16-16S-30W  
1250 feet from N Section Line, 1730 feet from W Section Line  
Lease Name: SCHADEL Well #: 21-16  
County: LANE Total Vertical Depth: 4570 feet

Operator License No.: 34038  
Op Name: FLATIRONS RESOURCES LLC  
Address: 303 E 17TH AVE STE 940  
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comments  
SURF 8.625 253 WITH 170 SX CMT

148.53

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2009 9:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: DUSTY RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2240' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 280' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 07/02/2009 11:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:  
1ST PLUG AT 2240' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 280' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:  
INVOICED  
DATE 8-31-09  
INV. NO. 2010060182

RECEIVED  
JUL 13 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OIL WELL CEMENTING.  
Plugged through: DP

District: 01  
Signed Michael Maier (TECHNICIAN)  
RECEIVED JUL - 7 2009 KCC DODGE CITY  
Form CP-2/3