

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23791-00-00
Spot: W2W2W2 Sec/Twnshp/Rge: 18-20S-22W
2640 feet from S. Section Line, 330 feet from W Section Line
Lease Name: GROSS WHITLEY Well #: 1
County: NESS Total Vertical Depth: 4335 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		WITH 190 SX CMT
DVT		1434		WITH 260 SX CMT 140.89
PROD	5.5	4318	0	100 SKS+260 SKS 60-40 POZ

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2009 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 277-2511

Proposed Plugging Method: AS PER KCC-RIH W/ SAND LINE TAG BOTTOM @ 4335'-SAND BACK TO 4280' TOP W/ 2 SKS CEMENT-RIH W/ TBG TO 1430'-SPOT 100 SKS 60-40 POZ W/ 4% GEL-POOH W/ TBG TO 275'-TOP OFF CSG TO SURFACE W/ 25 SKS 60-40 POZ W/ 4% GEL

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2009 2:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND TO 3880' & 2 SX CMT. RUN TBG TO 1430'. PUMP 100 SX CMT & 300# HULLS. PULL TBG TO 275'. WAIT 2 HOURS. PUMP 45 SX CMT. CMT CIRCULATED TO PIT. PULLED TBG & TOPPED OFF WITH 30 SX CMT. TIED ONTO BACKSIDE & PUMPED 2 SX CMT. PRESSURED TO 500# & HELD. CMT WAS FALLING SLOWLY. TOC @ 450'. TOPPED OFF WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4318	4335	OH	

INVOICED
DATE 8/31/09
INV. NO. 2010060185

KANSAS CORPORATION COMMISSION

JUL 27 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

JUN 30 2009

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

Form C-27

PKT