

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15131-00-00
Spot: SWSESE Sec/Twnshp/Rge: 34-16S-11W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: KRAUTWURST Well #: 5
County: BARTON Total Vertical Depth: 3390 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	108	0	w/unknown sxs cmt
PROD	5.5	3380	0	w/unknown sxs cmt <u>35</u>

110.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2009 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE PAYNE Company: HERMAN L. LOEB, LLC Phone: (618) 943-2227

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.
Emergency plug with rig over the hole - bad casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - tied to tubing - pumped 9 sxs gel then pumped 100 sxs cement with 300# hulls on bottom.
Pulled tubing to 1350' - pumped 100 sxs cement.
Pulled tubing to 650' - pumped 75 sxs cement - cement circulated to surface.
Pulled tubing - tied onto casing - pumped 25 sxs cement - cement circulated out backside to surface.
No head on surface pipe - could not squeeze.

Perfs:

INVOICED
DATE 8/31/09
INV. NO. 2010060187

RECEIVED
JUL 20 2009
KCC WICHITA

Remarks: BASIC CEMENTING COMPANY-TICKET #1718-0009A.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

HINKLE OIL COMPANY

5 KRAUTWORST

34-16-11W 53
SW SE SE

Contr. _____ BARTON _____ County

E 1942 Comm. 3-15-50 Comp. 5-19-50 IP 134 BOPD
PHY POT

Tops	Depth	Datum
LANS	3113	-1171
ARB	3380	-1438
T.D.	3390	-1448

Casing
 8" 108 SW 75 B0/10 HRS:
 5" 3380

KRAFT-PRUSA POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS