

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-2-61
JUN 21 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: CN 1/2 NE SE Sec. 9 Twp. 10 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3771

I have this date completed supervision of plugging of:

Lease Name: Baldwin Well No. 1

Operator's Full Name: Frank J. Black

Complete Address: Box 150 Mc Pherson, Kansas

Plugging Contractor R & D Casing Pulling Co

Address: Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 17 Month 6 Year 61

The above well was plugged as follows:

8 5/8" 169' circulated with cement - 5 1/2" 3771' with 120 sax cement - PB
3465' - perforated 3442'

Filled with sand to 3430', set 4 sax cement with dump bailer, pulled 1000'
5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (15 sax Gel).
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced
20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by R & D Company pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 6/23/61

INV. NO. 3270-W