

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
6-20-61
JUN 20 1961

File No. _____ CONSERVATION DIVISION _____
Wichita, Kansas

Location: SW NE SE Sec. 9 Twp. 10 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3753

I have this date completed supervision of plugging of:

Lease Name: Baldwin Well No. 2

Operator's Full Name: Frank J. Black

Complete Address: Box 150 Mc Pherson, Kansas

Plugging Contractor R & D Casing Pulling Co

Address: Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?
Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 14 Month 6 Year 61

The above well was plugged as follows:

10 3/4" 159' circulated with cement - 5 1/2" 3746' with 75 sax cement behind
PB 3577' - perf 3456'

Filled with sand to 3445', set 4 sax cement with dump bailer, pulled 680'
5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (20 sax Gel),
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced
20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by R & D Casing pulling pump truck.

Signed: Edon Petty
Conservation Division Agent

Reviewed: Harold Morris
Field Supervisor

Remarks:

INVOICED
DATE 6/23/61
INV. NO. 3271-W