

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION  
5-3-61  
MAY 3 1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks \_\_\_\_\_  
Location: SW SE SW Sec. 7 Twp. 10 Rge. 19 (E) (W) \_\_\_\_\_  
Name of Field: \_\_\_\_\_ Total Depth: 3769

I have this date completed supervision of plugging of:

Lease Name: Atherton Well No. 2

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor: Pipe Pulling Inc

Address: Great Bend, Kansas License No. 462

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 20 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 250' circulated with cement - 5 1/2" 3767' with 100 sax cement.

Filled with sand to 3721', set 5 sax cement with dump bailer, pulled 960'

5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500' ( 20 sax Gel)

displaced 20 sax cement through 5 1/2" at 450', heavy mud to 160', displaced

20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Pipe Pulling pump truck.

Signed: *Edson Petty*  
Conservation Division Agent

Reviewed: *Harold Wallis*  
Field Supervisor

Remarks:

INVOICED  
DATE 5/11/61  
INV. NO. 3059-W