

15-163-03370-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-3-61
MAY 3 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks
Location: NE SE SW Sec. 7 Twp. 10 Rge. 19 (E) (W)
Name of Field: _____ Total Depth: 5785

I have this date completed supervision of plugging of:

Lease Name: Atherton Well No. 4

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor: Pipe Pulling Inc

Address: Great Bend, Kansas License No. 462

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 22 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 250' circulated with cement - 5 1/2" 3780' with 125 sax cement
Filled with sand to 3770', set 5 sax cement with dump bailer, pulled 1026'
5 1/2" to 400', circulated hole with heavy mud through 5 1/2" at 460' (20 sax Gel),
displaced 20 sax cement through 5 1/2" at 460', heavy mud to 170', displaced
20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Pipe Pulling pump truck.

Signed: Edon Perry
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED
DATE 5/11/61
INV. NO. 3060-W