

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-28-61  
APR 28 1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rooks  
Location: NE NE SW Sec. 7 Twp. 10 Rge. 19 (E) (W) \_\_\_\_\_  
Name of Field: \_\_\_\_\_ Total Depth: 3752

I have this date completed supervision of plugging of:

Lease Name: Atherton Well No. 1

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor: Pipe Pullers Inc

Address: Ellinwood, Kansas License No. 462

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 25 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 250' circulated with cement - 5 1/2" ~~47~~ 3749' with 100 sax cement.  
Filled with sand to 3698' set 4 sax cement with dump bailer, pulled 1024'  
5 1/2" to 462', circulated hole with heavy mud through 5 1/2" at 462' ( 21 sax Gel )  
displaced 20 sax cement through 5 1/2" at 462', heavy mud to 160', displaced  
20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.

Mudding and cementing by Pipe Pulling Inc pump truck.

Signed: Jewel M. Ogden  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 5/10/61  
INV. NO. 3056-W