

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION  
5-3-61  
1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks  
Location: SW NE SW Sec. 7 Twp. 10 Rge. 19 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3769

I have this date completed supervision of plugging of:

Lease Name: Atherton Well No. 3

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor: Pipe Pullers Inc

Address: Great Bend, Kansas License No. 462

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 27 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 235' circulated with cement - 5 1/2" 3762' with 100 sax cement.  
Filled with sand to 3750', set 5 sax cement with dump bailer, pulled 922'  
5 1/2" to 475', circulated hole with heavy mud through 5 1/2" at 475' ( 21 sax Gel),  
displaced 20 sax cement through 5 1/2" at 475', heavy mud to 160', displaced 20  
sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.

Mudding and cementing by Pipe Pullers pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 5/11/61  
INV. NO. 3058-W