

RP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-4-65
MAY 4 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sohio Oil Co

Complete Address: Box 673 Russell, Kansas

Lease Name Dick Well No. 6

Location SE NW SE Sec. 7 Twp 10 Rge. (E) (W) 19

County Rooks Total Depth 3793

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Operation Completed: Hour 7PM Day 30 Month 4 Year 65

The Above well was plugged as follows:

8 5/8" 1655' circulated with cement - 5 1/2" 3789' with 150 sax cement.

Hole bridged at 2445' unable to drill bridge out - set 4 sax cement at

2445' with dump bailer - pulled 2290' 5 1/2" to 620', circulated hole with

heavy mud through 5 1/2" at 620' (17 sax Gel), displaced 20 sax cement

through 5 1/2" at 540', heavy mud to 200', displaced 20 sax cement through

5 1/2" at 200', heavy mud to 35', set 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Perry*
Well Plugging Supervisor

DATE 5/4/65

INV. NO. 1099-4