

15-163-01901-0000

Form CP-3  
Rev. 6-26-62

*10*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
5-6-65  
MAY 6 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Sohio Oil Co

Complete Address: Box 073 Russell, Kans

Lease Name Dick Well No. 2

Location SE SE SE Sec. 7 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3773

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Operation Completed: Hour 6PM Day 4 Month 5 Year 65

The Above well was plugged as follows:

8 5/8" 1630' circulated with 800 sax cement - 5 1/2" 3769' with 125 sax cement  
sand back to 3760', set 4 sax cement with dump bailer - pulled 3089'  
5 1/2" to 300' circulated hole with heavy mud through 5 1/2" at 600' ( 16 sax Gel)  
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 230', displaced  
20 sax cement through 5 1/2" at 230', heavy mud to 35', set 10 sax cement  
to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leon Perry  
Well Plugging Supervisor

DATE 5/9/65  
INV. NO. 1111-W