

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW SW NE

SEC. 9 TWP. 10 RGE. 19 *W*

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Henderson

Operator Walters Drng Co Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3745 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 167' circulated with cement - 5 1/2" at 3738' with 100  
sax cement behind.

Filled with sand tom 3720', set 4 sax cement with dump bailer,  
pulled 2000' 5 1/2" - hole was pumped full of commercial mud,  
set rock bridge at 165', 15 sax cement, mud to 40', set rock  
and 10 sax cement to bottom cellar.

District Conservation Agent

Date 12-31-55

1-3-56

**PLUGGING**  
FILE SEC 9-710-R19W  
BOOK PAGE 28 LINE 18